



The Corporation of the Town of Essex

Addendum 1

Request for Tender RFT-ID-23-010

Ridge Road Rehabilitation, Phase 1 - 2023

Closing Information:

Date: April 05, 2023

Time: 3:00.00 PM Local Time

Location: Town of Essex Municipal Offices
33 Talbot Street South
Essex, Ontario N8M 1A8

Question and Answer

Q.1: Per the CRM requirement the elevation of Ridge Road will be raised by 75 mm. Are the Granular Shoulders to be raised accordingly or will the town complete the shoulders with their own forces? Will there be a Pay item for this work if the contractor is to perform?

A.1: Item #6 under Provisional Items is added for the hauling and placement of granular shoulders in a per m cost (3000m estimated, 1500m long project length x 2 as both sides of the road require shouldering). The granular material will be supplied by the Town of Essex from our stockpile at 3980 North Malden Road in Essex. The winning Tenderer would be required to load the material from our yard into their stone hauler and bring it to the project site to place the shouldering.

Please refer to the revised Appendix A (copy attached) and please use this revised Appendix A to submit your tender.

END

27. Appendix A - Form of Tender (Revised)

RIDGE ROAD REHABILITATION, PHASE 1 - COUNTY ROAD 20 TO SOUTH OF HUFFMAN ROAD - REVISED MARCH 30, 2023

SCHEDULE OF ITEMS AND PRICES

Items shall include payment for supply and installation of all materials noted.

* PROVISIONAL

ITEM NO.	OPSS	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE	AMOUNT
SECTION 'A' - COLD RECYCLE ASPHALT						
1	PROV 334	Cold Recycle Asphalt Mix Paving (1500m x 7m x 75mm deep)	m ²	10,500	\$	\$
TOTAL - SECTION 'A' - COLD RECYCLE ASPHALT						\$
SECTION 'B' - SURFACE TREATMENT						
2	MUNI. 304 MUNI. 1006 PROV 1103	Double Surface Treatment (2023)	m ²	10,500	\$	\$
TOTAL - SECTION 'B' - SURFACE TREATMENT						\$
SECTION 'C' - PROVISIONAL WORKS						
*3	MUNI. 304 MUNI. 1006 PROV 1103	Single Surface Treatment (to be completed in 2024)	m ²	10,500	\$	\$
*4	PROV 334	Cold Recycle Asphalt Mix Paving Leveling Course	m ²	1,050	\$	\$
*5	MUNI. 304 MUNI. 1006 PROV 1103	Asphalt Escalation	Allow.	---	---	\$ 10,000.00
*6	MUNI. 314	Hauling & Placement of Granular Shoulder (approx. 500mm wide), including granular driveways. Town of Essex to supply granular material from stockyard at 3980 North Malden Road in Essex. The winning proponent would be required to load the material from our yard into their stone hauler and bring it to the project site to place the shouldering.	m	3000	\$	\$
TOTAL - SECTION 'C' - PROVISIONAL WORKS						\$

SUMMARY OF TENDER FOR SECTION A & SECTION B	
SECTION 'A' - COLD RECYCLE ASPHALT	\$
SECTION 'B' - SURFACE TREATMENT	\$
SUBTOTAL FOR SECTION A & SECTION B	\$
HST (13%)	\$
TOTAL TENDER PRICE FOR SECTION A & SECTION B (INCLUDING HST)	\$